Worcestershire County Council's and the Appellant's Response to the Rule 6 Party's Comments on the Draft Schedule of Conditions

---

Appeal by NRS Aggregates Ltd against the refusal of planning permission by Worcestershire County Council of

"Proposed sand and gravel quarry with progressive restoration using site derived and imported inert material to agricultural parkland, public access and nature enhancement on land at Lea Castle Farm, Wolverley Road, Broadwaters, Kidderminster, Worcestershire.

Planning Inspectorate Reference: APP/E1855/W/22/3310099

County Council Reference: 19/000053/CM

November 20204

Commencement

1) The development hereby approved must be begun not later than the expiration of 3 years beginning with the date of this permission.

ReasonRequired to be imposed pursuant to Section 91 of the Town and Country Planning Act 1990.

2) The operator shall provide written notification to the Mineral Planning Authority at least 5 working days prior to:-

i. The commencement of the development hereby approved;
ii. The commencement of soil stripping operations in any phase;
iii. The commencement of mineral extraction in any phase;
iv. The completion of mineral extraction in any phase;
v. The commencement of infilling operations in any phase;
vi. The completion of infilling operations in any phase;
vii. The commencement of soil replacement operations in any phase; and
viii. The completion of soil replacement operations in any phase.

should include all works, including formation of access, the formation is conditioned in terms of work required and so needs monitoring.

Response: Consider this requirement would be captured by Condition 2) Part i)

Time Limits

3) All mineral extraction operations shall cease, and the site shall be restored in accordance with the approved restoration scheme as required by Condition 46) of this permission, within 11 years of commencement of the development hereby approved. Should mineral extraction operations cease before this date, the Mineral Planning Authority shall be notified in writing within 1 month of mineral extraction operations ceasing.

The MPA needs to be informed of the completion of the restoration.

Response: Consider this requirement is captured by Condition 2) Part viii) relating to completion of soil replacement operations in any phase, together with Condition 49) relating to aftercare scheme, which includes a site meeting reviewing each year's aftercare works. It is in the appellant's own interest to notify the Mineral Planning Authority as soon as restoration is complete, to agree a site is entered into the aftercare, so that the 30-year aftercare period for each phase starts as soon as possible.

ReasonFor the avoidance of doubt and to assist with the monitoring of the planning permission.

Approved Plans

4) The development hereby approved shall be carried out in accordance with the details shown on the following approved drawings,

Drawing numbered: 5, reference number: KD.LCF.011, titled: 'Disturbed Land', dated: October 2019;

Drawing numbered: 6, reference number: KD.LCF.021, titled: 'Plant Site Layout – Plan & Elevations', dated October 2019;

Drawing numbered: 7, reference number: KD.LCF.022, titled: 'Plant Site Sections – Conveyor Routing beneath PORW 62 6(B)', dated October 2019;

Drawing numbered: 8A, reference number: KD.LCF.003A, titled: 'Initial Works', dated July 2021;

Drawing numbered: 9A, reference number: KD.LCF.004A, titled: 'Phase 1 – Working & Restoration', dated July 2021;

Drawing numbered: 10A, reference number: KD.LCF.005A, titled: 'Phase 2 – Working & Restoration', dated July 2021;

Drawing numbered: 11A, reference number: KD.LCF.006A, titled: 'Phase 3 – Working & Restoration', dated July 2021;

Drawing numbered: 12A, reference number: KD.LCF.007A, titled: 'Phase 4 – Working & Restoration', dated July 2021;

Drawing numbered: 13A, reference number: KD.LCF.008A, titled: 'Phase 5 – Working & Restoration', dated July 2021;

Drawing numbered: 14A, reference number: KD.LCF.009A, titled: 'Final Works', dated July 2021;

Drawing numbered: 15B, reference number: KD.LCF.010B, titled: 'Concept Restoration', dated July 2021;

Drawing numbered: 16A, reference number: KD.LCF.028A, titled: 'Restoration Sections', dated October 2020;

L&R Figure 5A, reference number: KD.LCF.026A, titled: 'Current & Proposed Public Rights of Way', dated July 2021;

Reference number: KD.LCF.032, titled: 'Surface Water Management', dated September 2020;

Reference number: KD.LCF.033C, titled: 'Public Rights of Way Proposed', dated July 2021;

Reference number: KD.LCF.034C, titled: 'The Post Restoration PROW Routes within and adjacent to the Site', dated July 2021;

Reference number: KD.LCF.035, titled: 'Bund 2: Tree Root Protection Areas', dated September 2020;

Reference number: KD.LCF.036, titled: ‘Restoration Sections – The Avenue’, dated September 2020;

Reference number: KD.LCF.041, titled: ‘Typical Sections through land around Tree 22’, dated April 2021;

Reference number: KD.LCF.042, titled: ‘Root Protection: Existing Avenue Trees’, dated July 2021;

Supporting Statement for the Conveyor Underpass Under Crossing of Bridleway Number 626 on Land Known as Lea Castle Farm, Wolverley, Worcestershire drawing

5) No mineral extraction shall take place outside the limit of the extraction boundary shown on drawing numbered: 4A, reference number: KD.LCF.013A, titled: 'Proposals Plan', dated July 2021.

On KD.LCF.013A (CD5.03) there is no extraction boundary as referred to in the condition.

ReasonFor the avoidance of doubt and to assist with the monitoring of the planning permission.

Response: Noted, the dashed line shows the limit of extraction. Condition proposed to be amended as follows:

*No mineral extraction shall take place outside the limit of the extraction boundary**, as indicated by the black dashed line and blue hatched Initial Works Phase,** shown on drawing numbered: 4A, reference number: KD.LCF.013A, titled: 'Proposals Plan', dated July 2021.*

Waste Acceptance

6) No waste materials other than those defined in the application, namely construction, demolition and excavation wastes shall be imported to the site for infilling and restoration purposes.

Reason:To define the permission.

Phasing

7) The site shall be progressively worked and restored in accordance with the phased working n6

Reason: To ensure that the site is reclaimed in a condition capable of beneficial after use at an early date and in the interests of amenity, in accordance with Policies MLP 11, MLP 26, MLP 28, MLP 33, and MLP 35 of the adopted Worcestershire Minerals Local Plan, Policies WCS 5, WCS 9, WCS 11, and WCS 12 of the adopted Worcestershire Waste Core Strategy, and Policies SP.20, SP.22, SP.23, SP.28, and DM.26 of the adopted Wyre Forest District Local Plan.

Depth of Working

8) No excavation or extraction shall take

The MacDonalds and others need alerting if the site is being worked to give them notice their weekend or public holiday will be ruined.

Response: No working should be taking place outside of the hours above. It should be very rare (if ever) the Appellant would need to work outside of these hours.

It is common practice that the Community Liaison Group or local residents are informed by the Council or by the appellant (at the Council's request) in such events, but it is not considered it is necessary to capture this requirement in a condition.

Reason: To protect the amenity of adjacent residential properties, in accordance with Policy MLP 28 of the adopted Worcestershire Minerals Local Plan, and Policy WCS 14 of the adopted Worcestershire Waste Core Strategy, and Policy SP.33 of the adopted Wyre Forest District Local Plan.

Design of Plant

10) Notwithstanding the submitted details, detailed design drawings of all plant, structures, buildings, including the conveyors to be sited at the site shall be submitted to and approved in writing by the Mineral Planning Authority prior to their erection / construction on site. Details shall include dimensions, materials, colour, and finishes. The development shall be carried out in accordance with the approved details, and shall be retained and maintained as such thereafter.

Response: This condition is wider than just plant, and includes plant, structures, buildings and conveyors.

Reason: To maintain the visual and environmental quality of the site, in accordance with Policies MLP 28 and MLP 33 of the adopted Worcestershire Minerals Local Plan, Policies WCS 12 and WCS 14 of the adopted Worcestershire Waste Core Strategy, and Policies SP.20 and DM.24 of the adopted Wyre Forest District Local Plan.

Highways and Public Rights of Way

“No soil stripping operations shall take place within the Initial Works Phase, as shown on drawing numbered: 4A reference number: KD.LCF.013A, titled: ‘Proposals Plan’, dated July 2021, until…”.

The term HGV needs to be defined as vehicles over 3.5 tonnes

Response:

15) All sand and gravel worked in Phases 1 to 3 as shown on drawing numbered: 4A, reference number: KD.LCF.013A, titled: 'Proposals Plan', dated July 2021, and all imported inert materials to restore Phases 1 to 3, shall only be transported across Bridleway WC-626 to and from the plant site by the approved below ground conveyor, as required by Condition 14) of this permission.

Reason: To define the permission and to protect users of the Public Rights of Way, in accordance with Policy MLP 30 of the adopted Worcestershire Minerals Local Plan.

16) Within 3 months of the commencement of the development hereby approved, the specification, location and timetable for the provision of at least 1 electric vehicle charging space to be provided within the plant site, as shown on drawing numbered: 6, reference

v. Details of signage requiring all HGVs to turn left onto Wolverley Road (B4189) along with the siting of the signage close to the site exit, and a programme for its installation and maintenance; and

vi. All HGVs used for export of minerals or the importation of inert materials to and from the site, shall be fitted with Global Positioning System (GPS) tracking equipment, and this tracking information shall be recorded and made available to the Mineral Planning Authority within 7 days of a written request. All such records shall be kept for at least 12 months from the date they were recorded.

sg3 804C 36 Td [v..5 4C 36 Td [hJ 1.23.i

Response: Unsure what the above comment is referencing. It is presumed it may relate toJ 0.004 T/TT1 1 Tf 0.007 .5 (at)-7.2e2 (e t)-7 (s)-17.9 (t)]TJaf-d2e 6 0.003 4t0.003 3T

under Section 25 Highways Act 1980 has been completed and advertised as dedicated as routes on the Definitive Map.

Until the PRoW diversions are approved, can't set a programme. None of this will overcome the concerns regarding (i) conflict of PROW users with traffic inside the site; (ii) conflict of PROW users with the busy main road around the site; (iii) lack of security over a "permissive bridleway" – that is ultimately a private arrangement, which cannot be secured by this planning permission. This will also not ensure that the public enjoyment of the PROWs is maintained as there is no proposal for monitoring, or for conditions managing impacts along the PROW.

Response: Noted. It is considered that this can be secured by condition as set out in this Schedule of Conditions.

Reason: To enhance public access across the site, and to ensure conformity with summited details, in accordance with Policies MLP 7 and MLP 30 of the adopted Worcestershire Minerals Local Plan.

Reason for the pre-commencement condition: The provision of new routes and upgrading of existing public rights of way are one of the first operations to take place on site, so it is important that such details have been submitted and approved prior to the commencement of the development, for the reasons stated above.

21) Notwithstanding the submitted details, prior to the commencement of the development hereby approved, a scheme and programme for the proposed public access routes shown as 'Proposed New Permissive Bridleways' on drawing: L & R Figure 5A, Ref: KD.LCF.026A titled: 'Current & Proposed Public Rights of Way', dated July 2021, shall be submitted to and approved in writing by the Mineral Planning Authority. The scheme and programme for the proposed public access routes shall include details of:

i. The alignment and width of the proposed public access routes;
ii. Surfacing materials;
iii. Drainage provision;
iv. Details of any gates, fences or barriers;
v. Maintenance arrangements; and
vi. Timetable for their implementation.

Show how and where external lighting will be installed, through provision of appropriate technical specifications including optic photometric data and contour plans (in both horizontal and vertical planes), and glare rating, so that it can be clearly demonstrated that areas to be lit will not disturb or prevent the above species using their territory or having access to their breeding sites and resting places.

Thereafter, the development shall be carried out and maintained in accordance with the approved details. Under no circumstances shall any other external lighting be installed without prior consent from the Mineral Planning Authority.

Lighting should be l f <</().8 ( )]TJ -0.007 Tw 0 -1.815 T( )-10.3 (C /4.9 (inhID 7 >>10.5 (n)2.1)9.5 (e)-3.27)-

1:1250, with all levels related to Ordnance Datum. The surveys shall include the extent of land open for quarrying or undergoing restoration and quarry floor levels.

ReasonFor the avoidance of doubt and to assist with the monitoring of the planning permission.

Water Environment

26) No mineral extraction shall take place until a groundwater, surface water level and quality, monitoring scheme has been submitted to and approved in writing by the Mineral Planning Authority. Thereafter the scheme shall be implemented in accordance with the approved details. The Scheme shall include, but may not be limited to:

    i. Pre-commencement, operational (extraction phase) and post extraction monitoring, of the existing onsite monitoring boreholes identified in Environmental Statement Volume 2 –

Reason: To protect the water environment and prevent pollution, in accordance with Policy MLP 37 of the adopted Worcestershire Minerals Local Plan, Policy WCS 10 of the adopted

viii. Noise level monitoring results shall be submitted to the Mineral Planning Authority within 7 days of the noise monitoring being carried out;

ix. If the noise level monitoring results reveal an exceedance of the relevant noise limits set out in Conditions 30) or 31) of this permission, then no further mineral extraction or infilling operations shall take place until a scheme providing for further noise mitigation has been submitted to and approved in writing by the Mineral Planning Authority, and the approved noise mitigation measures have been subsequently implemented. Further noise level monitoring shall be undertaken within 7 days of the implementation of the further noise mitigation and submitted to the Mineral Planning Authority within 7 days of the noise level monitoring being carried out. If the subsequent noise level monitoring results still reveal an exceedance of the relevant noise limits set out in Conditions 30) or 31) of this permission, then the provisions and process set out in this Condition, Part ix shall be repeated until compliance with the noise limits has been achieved;

x. A procedure for the logging, investigating and responding to noise complaints whether received directly from a member of the public or via the Mineral Planning Authority; and

xi. If, following a complaint, the Mineral Planning Authority decides that further noise level monitoring -3 (c)8.9T/ (l)5Wral Plniolnrelevera.685 0n i.3 (8)7.8 (ra.685 0n)2.3P dia the Mineral

30) The noise attributable to mineral operations from the site shall not exceed the levels set out below at the receptor locations identified in the Noise Assessment Report, dated 12 September 2019 when measured in terms of an LAeq 1-hour level (free field):

Broom Cottage: LAeq, 1-hour 53dB;
South Lodges: LAeq, 1-hour 55dB;
Heathfield Knoll: LAeq, 1-hour 55dB;
Brown Westhead Park: LAeq, 1-hour 46dB;
The Bungalow: LAeq, 1-hour 45dB;
Keeper's Cottage: LAeq, 1-hour 49dB; and
Castle Barns: LAeq, 1-hour 51dB.

Reason: To control dust emissions, in accordance with Policies MLP 28 and MLP 29 of the

Reason: To ensure soils are managed and conserved for beneficial purposes to ensure the satisfactory restoration of the site, in accordance with Policies MLP 34 and MLP 35 of the adopted Worcestershire Minerals Local Plan.

38) All topsoil, subsoil and overburden shall be stored in separate bunds which:

i. Shall be constructed with only the minimum amount of soil compaction to ensure stability and so shaped as to avoid collection of water in surface undulations;
ii. Shall not be traversed by heavy vehicles or machinery except where essential for the purposes of bund construction or maintenance;
iii. Shall not be subsequently moved or added to until required for restoration;
iv. Shall have a minimum 3 metre stand-off buffer of undisturbed ground around each storage bund;
v. Shall only store topsoil on like textured topsoil and subsoil on like textured subsoil; and
vi. Topsoil bunds shall not exceed 3 metres in height, subsoil bunds shall not exceed 5 metres in height, and overburden bunds shall not exceed 6 metres in height.

Reason: To ensure soils are managed and conserved for beneficial purposes to ensure the satisfactory restoration of the site, in accordance with Policies MLP 34 and MLP 35 of the adopted Worcestershire Minerals Local Plan.

39) No plant or vehicles shall cross any area of unstripped soil or subsoil, except where such trafficking is essential for the purposes of undertaking permitted operations. Essential traffic routes shall be marked in such a manner as to give effect to this condition. No part of the site shall be excavated, traversed or used as a road for the stationing of plant or buildings or for the storage of subsoil, overburden, waste or mineral deposits, until all available topsoil has been stripped from that part. The exceptions are that topsoil may be stored on like topsoil and subsoil may be stored on like subsoil.

Reason: To ensure soils are managed and conserved for beneficial purposes to ensure the satisfactory restoration of the site, in accordance with Policies MLP 34 and MLP 35 of the adopted Worcestershire Minerals Local Plan.

40) Prior to the commencement of soil stripping operations, a scheme for seeding and management of all soil and overburden storage bunds that will remain in situ for more than 3 months or over winter shall be submitted to and approved in writing by the Mineral Planning Authority. Seeding and management of the storage bunds shall be carried out in accordance with the approved scheme.

Reason: To control plant growth and prevent the build-up of a seed bank of agricultural weeds, or their dispersal onto adjoining land and to ensure that the site is reclaimed to a condition capable of beneficial afteruse at an early date, in accordance with Policies MLP 7, MLP 11, MLP 31, MLP 33, MLP 34 and MLP 35 of the adopted Worcestershire Minerals Local Plan, Policies WCS 5, WCS 9, WCS 11 and WCS 12 of the adopted Worcestershire Waste Core Strategy, and Policies SP.20, SP.22, SP.23, SP.28, and DM.26 of the adopted Wyre Forest District Local Plan.

Ecology

41) Notwithstanding the submitted details, prior to the commencement of the development hereby approved, a detailed Construction Environmental Management Plan (CEMP) for biodiversity shall be submitted to the Mineral Planning Authority for approval in writing. The CEMP for biodiversity shall include the following:

i. Risk assessment of potentially damaging quarrying activities to habitat and wildlife;
ii. Identification of "biodiversity protection zones", including tree root protection zones to be protected by suitable fencing in accordance with BS5837:2012;
iii. Practical measures (both physical measures and sensitive working practices) to avoid or reduce impacts to habitat and wildlife during quarrying (may be provided as a set of method statements);
iv. The location and timing of sensitive works to avoid harm to habitat and wildlife;
v. The times during the works when specialist ecologists need to be present on site to oversee works;
vi. Responsible persons and lines of communication;
vii. The role and responsibilities on site of an ecological clerk of works (ECoW) or similarly competent person; and
viii. Use of protective fences, exclusion barriers and warning signs to avoid harm to retained habitat and wildlife.

adequate baseline of conditions prior to start of development, including provision of Habitat Condition Assessment sheets to describe baseline condition of all habitats retained and enhanced;

iii. Extent and location / area of proposed enhancement works on appropriate scale maps and plans to include any mitigation and enhancement measures such as bat and / or bird boxes;

iv. Ecological trends and constraints on site that might influence management;

v. Methods for data gathering and analysis;

vi. Location, timing and duration of monitoring;

vii. Responsible persons and lines of communication;

viii. Appropriate success criteria, thresholds, triggers and targets against which the effectiveness of the various conservation measures being monitored can be judged, to include reference (where appropriate) to the target condition of habitats and hedgerows;

ix.

and MLP 33 of the adopted Worcestershire Minerals Local Plan, Policies WCS 9, WCS 11, and WCS 12 of the adopted Worcestershire Waste Core Strategy, and Policies SP.20, SP.22, SP.23, SP.28, DM.24 and DM.26 of the adopted Wyre Forest District Local Plan.

Reason for the pre-commencement condition: A BEMMP is required prior to the commencement of the development, as it requires the identification of an adequate habitat baseline conditions prior to the start of development, for the reasons stated above.

Landscape

43) Notwithstanding the submitted details, prior to the commencement of the development hereby approved, a Landscape and Ecological Management Plan (LEMP) shall be submitted to and approved in writing by the Mineral Planning Authority. Thereafter, the development shall be carried out in accordance with the approved details. The LEMP shall comprise of a drawing and document that covers:

i. Aims and objectives of the scheme;
ii. A plan with annotations showing the landscape and habitat or features to be retained, created and managed, including detailed advanced planting scheme

removed by the development, they shall be replaced with like species and equivalent size, which in the case

Reason for the pre-commencement condition: To ensure suitable protection of the important Tree Preservation Order trees of T9 and T10, and as their retention may inform how earlier phases of the development are worked and the site restored.

Restoration

46) Notwithstanding the submitted details, prior to the commencement of the development hereby approved, a detailed restoration scheme for the site, based on drawing numbered: 15B, reference number: KD.LCF.010B, titled: 'Concept Restoration', dated July 2021, but updated to take account of the retention of trees T9 and T10 as shown on drawing numbered: TS71-004, titled: 'Tree Protection & Removal Plan 2', dated May 2019 in the Environmental Statement Volume 2 'Technical Appendix C – Arboriculture', shall be submitted to the Mineral Planning Authority for approval in writing. The detailed restoration scheme shall include final contour levels, with all levels related to Ordnance Datum. Thereafter, the development shall be carried out in accordance with the approved scheme.

Reason: To ensure satisfactory restoration of the site, in accordance with Policies MLP 7, MLP 11, MLP 31, and MLP 33 of the adopted Worcestershire Minerals Local Plan, Policies WCS 5, WCS 9 and WCS 12 of the adopted Worcestershire Waste Core Strategy, and Policies SP.20, SP.22, SP.23, SP.28, DM.24, and DM.26 of the adopted Wyre Forest District Local Plan.

Reason for the pre-commencement condition: A detailed restoration scheme

Response: Noted. However, this is common practice on mineral permissions, see for example a fairly recent appeal decision:

Reason: To support climate change mitigation, in accordance with Policy MLP 26 of the adopted Worcestershire Minerals Local Plan, and Policy SP.37 of the adopted Wyre Forest District Local Plan.

Permitted Development Rights

52) Notwithstanding the provisions of Class L of Part 7 and Class A and Class B of Part 17 of Schedule 2 of The Town and Country Planning (General Permitted Development) (England) Order 2015 (as amended) (or any order revoking, re-enacting or modifying that Order), no fixed or mobile plant, machinery, buildings, structures, erections or private ways shall be erected, extended, installed, rearranged, replaced or altered within the site without the approval of the Mineral Planning Authority.

LPA regularly remove pd rights to protect GB from further harm. PD rights for temporary uses like motorsport need to be removed and other rights which would cause further harm to the openness of the GB or amenity.

Response: Noted, but considered this goes out of scope of this appeal and would not pass the tests of conditions, as not relevant to this development. This is seeking to prevent an existing activity.

Reason: To protect the visual amenity of the site and the surrounding area, in accordance with Policies MLP 28 and MLP 33 of the adopted Worcestershire Minerals Local Plan, Policies WCS 12 and WCS 14 of the adopted Worcestershire Waste Core Strategy, and Policies SP.20 and DM.24 of the adopted Wyre Forest District Local Plan.

ReasonIn the interests of highway safety and to define the permission, in accordance with Policy MLP 39 of the adopted Worcestershire Minerals Local Plan, Policy WCS 8 of the adopted Worcestershire Waste Core Strategy, and Policy SP.27

Reason for the pre-commencement condition: To enable the local community to be informed of each stage of the development.

Planning Permission

57) A copy of this decision notice, together with all approved plans and documents required under the conditions of this permission shall be maintained at the site office at all times throughout the duration of the development and shall be made known to any person(s) given responsibility for management or control of activities/operations on the site.

Reason: To define the permission and to enable the monitoring of the consent in the interests of the amenity of the surrounding area, in accordance with Policy MLP 28 of the adopted Worcestershire Minerals Local Plan, Policy WCS 14 of the adopted Worcestershire Waste Core Strategy, and Policy SP.33 of the adopted Wyre Forest District Local Plan.